

	LED Down lighter as per client specification
	Single wall mounted light switch to be mounted at 1300mm above ufl.
	Double wall mounted plug, top of socket to be 1250mm above ufl
	Double wall mounted plug, top of socket to be 300mm above ufl
	(5 Watt x 2) Internal LED Wall mounted light

[illegible]

All dimensions to be checked on site before construction commences. All dimensions are given in millimeters, unless otherwise stated. All dimensions are to be in accordance with the applicable building codes, standards, and regulatory regulations and requirements. Contractors to be a suitably qualified and registered participant in the construction industry and to be suitably qualified to interpret and understand the drawings and read in conjunction with the clients OHS (Occupational Health and Safety) file. All work to be done in accordance with the relevant codes of practice and standards. Contractors to be priced if the contractor's responsibility to ensure he is familiar with the site. All trade names quoted may only be substituted with an equivalent name of a different manufacturer to be installed in strict accordance with manufacturer's specifications. Contractors to be responsible for ensuring that all work is to be fitted to comply with the relevant code of practice as specified in SANS 10400: Part O. All new work to be made good to the existing standard of the building. Contractors to be advised H. Gouws renders. All existing dimensions not to be scaled from drawings but to be checked on site. Any discrepancies shall be reported to the architect prior to commencement of work. Top of foundation to be a minimum of 150mm below finished ground level. All dimensions to be taken from the finished ground level. Drawings to be on 250mm thick "gunpals" i.e. green damp on 50mm sand binding layer and on well compacted fill in layers not more than 100mm thick. All dimensions to be taken from the finished works, window cills and at changes in floor level. These architectural drawings to be read in conjunction with the engineers drawings and specifications. All dimensions to be taken from the works. All building work to be carried out in accordance with the national building standards and specifications. Contractors to be responsible for their own local inspectors and pay all fees in connection therewith. All drainage work to be carried out in accordance with the relevant codes of practice and standards. Contractors to be responsible for the correct setting out of the building on site by a roof specialist prior to roof construction. All life layouts to be confirmed by architect prior to commencing. Levels to be taken from the finished ground level. All dimensions to be taken from the actual level, but a benchmark to base other heights of the building shown on the drawings. Contractors to be responsible for the correct setting out of the building on site with reference to the building line and boundaries. Contractor to be responsible for the correct setting out of the building on site with reference to the building line and boundaries. Contractor to be responsible for the correct setting out of the building on site with reference to the building line and boundaries. Contractor to be responsible for the correct setting out of the building on site with reference to the building line and boundaries.

101

